MYSORE DIVISION.

The 19th March 1906.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 8th April 1906, for restoring Halebede tank of R. No. 821, Hunsur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1907.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 (two hundred) in cash as earnest money, and be superscribed "Tender for restoring Halebede tank, Hunsur Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract quantity of Restoring Halebede Tank, Registered No. 821, Hunsur Taluk :—

Items of work	Per	Quantity
Bund—		
Earthwork to bund	C. yds.	1,569
Clearing silt	,,	6,538
Earthwork to breach, filling	,,	14,373
Puddle wall	,,	560
Turfing slopes	Sqr. yds.	3,919
New stone work revetment	C. yds.	1,459
Old stone work	,,	319
Gravel backing	,,	441
Removing and refixing old grade stone with bed slabs	No.	14
New grade stones with bed slabs	,,	9
New index stones	,,	23
New B. M. stone	,,	2
Registered No. stone	,,	1
Gauge stones	,,	1
Date stones	,,	1
Bailing water.	Lump sum	Rs.
Sluice—		
Opening and refilling, examining and repairing sluices	No.	2
Left Waste Weir 160′ long—		
Earthwork, excavation, gravelly and soft	C. yds.	1,096
Brick in mortar	C. ft.	1,018
Plastering with mortar	Sqrs.	7·08
Burnt stone slabs	S. ft.	353
Clearing approach (soft rock)	Lump sum.	

V. V. KARVE, for *Executive Engineer.*

CHANNELS DIVISION.

The 24th March 1906.

The attention of the public is invited to the notification published on page 423 of the *Mysore Gazette*, Part II, dated 22nd March 1906, regarding the tenders required for the extension of Chamraj Channel beyond Hosagrahar.

V. AIYASWAMI IYER,
Executive Engr., Channels Dn.